# IAO STREAM FLOOD CONTROL PROJECT REPAIRS WAILUKU, MAUI, HAWAII

# PUBLIC INFORMATION MEETING (3 OF 3)

Jessie Paahana, Environmental Coordinator Jessica Brunty, Lead Engineer Civil & Public Works Branch Honolulu District

26 August 2021











### **MEETING INFO**

Purpose: Share known details of the proposed structural repairs at two locations within the Iao Stream Flood Control Project channel

## Agenda:

- 1) Housekeeping/Introductions (5 min)
- 2) Review Documents Overview (15 min)
- 3) Proposed Action (15 min)
- 4) Project Schedule (5 min)
- 5) Open for comment (15 min)
- 6) Close (5 min)






### HOUSEKEEPING

#### WebEx features

- Mute/Double Mute
- Chat
- Raise Hand

#### Ways to comment:


- Orally
- WebEx Chat
- Email to CEPOH-PLANNING@usace.army.mil
- COMMENT PERIOD ENDS 9/13





## **INTRODUCTIONS**

- Nani Shimabuku, Project Manager, Civil Works Branch, Honolulu District (<u>Lorayne.p.Shimabuku@usace.army.mil</u>)
- Jessica Brunty, Lead Engineer, Civil Works Technical Branch, Honolulu District (Jessica.r.wiggs@usace.army.mil)
- Jessie Paahana,
   Environmental Coordinator,
   Civil Works Branch, Honolulu District
   (Jessie.k.Paahana@usace.army.mil)





#### **REVIEW DOCUMENTS**



# 1. ENGINEER DESIGN REPORT (EDR) AMENDMENT

- Engineering Document
- 2017 EDR
- →Updated modelling→Updated repairs
- Purpose: document Corps' engineering analysis, preliminary concept design, updated cost estimates, economic and safety analysis for proposed repairs to address design deficiency

# 2. SUPPLEMENTAL ENVIRONMENTAL ASSESSMENT

- Environmental NEPA Document
- 2017 EA + FONSI
- →Updated repairs→Updated analysis
- Purpose: document Corps' consideration of environmental effects of proposed repairs to address design deficiency

► BOTH require public review
Review Comment Period Closes 9/13/2021

# **ENGINEERING HISTORY**



Project Constructed (1981) Design Deficiency Report (1995) Engineering Documentation Report (2017)

2017 EA

General Reevaluation Study (2018-2020)

**EDR** 

**Amendment** 


(2021)

2021 SEA



# IAO STREAM FCP





#### **ALTERNATIVES**

- No Action Alternative
- Alternative 2: Remove Revetment X
- Alternative 6: Install Pre-Formed Scour Hole
- Alternative 11: Non-Structural Plan (Flood Warning System)
- Alternative 12\*: Combination
   Plan (Alternatives 2 + 6 + 11)





# **ALTERNATIVE 2: REMOVE REVETMENT X**










# **ALTERNATIVE 2: REMOVE REVETMENT X**








# **ALTERNATIVE 6: PRE-FORMED SCOUR HOLE**









### **ALTERNATIVE 11: FLOOD WARNING SYSTEM**



- Non-Structural Plan
- Will coordinate w/County of Maui Department of Emergency Management to establish a central and/or field office w/necessary software and equipment
- Purpose: to provide notice to Wailuku community of impending flood



# **ALTERNATIVE 12: COMBINATION PLAN**



- PREFERRED ALTERNATIVE
- Combines Alternative 2 + 6 +11
- Geographically, Hydraulically Distinct
- Single contract



### **ENVIRONMENTAL COMPLIANCE**



- NEPA: Supplemental Environmental Assessment, Anticipated FONSI
  - Minimal work within existing footprint, minor modification, restores function
- Opportunities to comment:
  - Preparation of Draft EA (closed)
  - Draft EA (open til 9/13)
  - CZM Public Notice (open til 9/7)
  - Notice of Availability Final EA/FONSI (notification only, no comment)



#### **ENVIRONMENTAL COMPLIANCE**



- > Section 106, NHPA: No Historic Properties Affected
  - Consulting parties: SHPD, County of Maui, Office of Hawaiian Affairs, Aha Moku Council, Maui Hawaiian Civic Club, Hui o Na Wai Eha
  - Consultation letters signed 8/26, mailing 8/27
- > Section 7, ESA w/USFWS: No Effect
- CZMA Federal Consistency Determination: Consistent w/State CZM Policies & Objectives
  - Initiated 7/27; Ongoing, seeking concurrence
- Section 401 CWA Letter of Confirmation: Coordinating w/DOH to obtain 401 WQC in Design Phase



# **NEPA SCHEDULE**



Task	Timeline
Draft SEA/EDRA Public Review (32 days)	8/12/21 — 9/13/21
Final EDRA and SEA/FONSI (anticipated)	9/30/21

Next Step: If approved for construction, then design and construction phase



# QUESTIONS? COMMENTS?





