

# U.S. Army Corps of Engineers - Honolulu

NAICS	EST ADVERTISE	PROJECTED AWARD DATE	Solicitation #	PROJECT TITLE	PROJECT DESCRIPTION	PROJECT LOCATION	EST AWARD VALUE	SET-ASIDE CATEGORY	PROJECTED PROCUREMENT METHOD
236115	FY18 4Q	FY18 4Q	TBD	Family Housing Replacement (DB)	Construct news housing units and demo 34 existing housing units	Kwajalein	\$25M - \$100M	TBD	TBD
236220	FY18 3Q	FY18 4Q	<a href="#">W9128A-18-B-0005</a>	Repair North Drainage, Electrical and Telecomm	Design-bid-build project to repair the Northern drainage system of the PTA cantonment to enable a more efficient system to divert runoff away from buildings on and off the cantonment. This will be accomplished by a combination of mortared riprap channels, gabion mattress lined swales, trench drains, permeable paver vehicle areas, infiltration beds, and drain sumps. All overhead secondary electrical lines will be replaced with new underground electrical lines. Telecommunications infrastructure will also be brought underground to accommodate future facility replacement.	Island of Hawaii (Pohakuloa Training Area)	\$10M - \$25M	SB	IFB
236220	FY18 4Q	FY18 4Q	TBD	Controlled Humidity Warehouse (DBB)	Construct an aviation parts storage facility to store class IX aviation parts to reduce loss caused by corrosion due to improper storage in highly corrosive environments. Include aviation parts storage, administrative space, information systems, fire protection and alarm systems, and energy monitoring control system (EMCS) connection. Supporting facilities include site development, utilities and connections, lighting, paving, parking, walks, curbs and gutters, storm drainage, information systems, landscaping and signage. Heating and air conditioning will be provided by self-contained systems or connection to the existing energy plant, etc.	Oahu (Wheeler AAF)	\$1M - \$10M	TBD	TBD
236220	FY18 4Q	FY19 1Q	TBD	Readiness Training Complex (Blocks A & B)	New Construction Demolish and replace outdated training facilities. Construct ten non-standard transient training barracks; 4 shower/latrines facilities, 2 company headquarters, 1 latrine, and 1 laundry building.	Island of Hawaii (Pohakuloa Training Area)	\$10M - \$25M	SB	RFP LPTA
236220	FY18 4Q	FY18 4Q	TBD	Repair Tower 1, 2, and 3 Catwalks	Construct new landing and stairway from exterior door leading to top of the towers, to include permanent safety railing on the stairway side of the tower. The new stairway will need to be extended an additional full stair width away from the tower in order to make room for new catwalk area and a new permanently installed railing that will be a sufficient space from the televiewer's area of travel.	Maui (Haleakala)	< \$1M	TBD	TBD
236220	FY19 1Q	FY19 1Q	TBD	Repair Bldg 2091	Renovate Building 2091 to support the 25th Infantry Division (25ID) staff. Repairs will address communications, power, lighting, HVAC, partitions for security, privacy, and noise abatement.	Oahu (Schofield Barracks)	\$10M - \$25M	TBD	RFP LPTA
236220	FY19 2Q	FY20	TBD	Replacement Bldg 8500	Replacement of Bldg 8500 at the JOTC on East Range	Oahu (Schofield Barracks)	TBD	236220	TBD
236220	TBD	TBD	TBD	Kunia Tunnel Upgrade Mechanical Distribuion System System Phase 3 (DBB)	Work Includes installing turnstiles, sally port, vehicle barrier, security fencing, asphalt paving, gravel roads concrete pathways, security cameras, lighting, signage, and demolition of existing features as needed.	Oahu (Kunia)	\$1M - \$10M	TBD	TBD
236220	TBD	TBD	TBD	Richardson Theater Catwalk System	Structural / Electrical interior renovation (Historic Building) Upgrade existing electrical and theater lighting system in the Richardson Theater including consolidating the existing electrical panels into one panel, provide new theater lighting and demolish all unnecessary circuits, wiring, fixtures and components. Repair and install new overhead catwalk systems to provide safe access for maintenance personnel. Catwalks shall include fall protection tie-offs safety rails, and any other safety features. New catwalk system shall allow personnel to reach all ceiling lighting fixtures safely.	Oahu (Ft Shafter)	\$1M - \$10M	236220	TBD
237990	FY18 4Q	TBD	TBD	Hawaii Water Management, Waiahole Reservoir (DBB)		Oahu	TBD	TBD	TBD

# U.S. Army Corps of Engineers - Honolulu

NAICS	EST ADVERTISE	PROJECTED AWARD DATE	Solicitation #	PROJECT TITLE	PROJECT DESCRIPTION	PROJECT LOCATION	EST AWARD VALUE	SET-ASIDE CATEGORY	PROJECTED PROCUREMENT METHOD
237990	FY18 4Q	FY19 1Q	TBD	Repair Lyman Drainage,	Provide erosion control repairs for the storm drainage ditches along Lyman Road and Humphreys Road. Re-grade storm drainage ditches, debris removal, plant vegetation and install erosion control blanket.	Oahu (Schofield Barracks)	\$1M - \$10M	237310	TBD
237990	TBD	TBD	TBD	Honolulu Harbor Phase II Maintenance Dredging (DBB)		Oahu (Honolulu Harbor)	TBD	237990	IFB
238210	FY19 1Q	FY19 1Q	<a href="#">W9128A-18-R-0010</a>	Energy Conservation Improvement Program (ECIP) 325KW PV System & Storage	Design-Build RFP for the design and construction of a 325KW (dc rated) photovoltaic (PV) system and a 150wKh battery storage system for the U.S. Army Reserve Center	American Samoa	\$1M - \$10M	Unrestricted	RFP
238210	TBD	TBD	TBD	Repair Electrical Vault		Oahu (Wheeler AAF)	TBD	238210	TBD
267990	FY18 4Q	FY18 4Q	<a href="#">W9128A-18-B-0004</a>	Nawiliwili Harbor Phose II Maintenance Dredging (DBB)	Clamshell Dredging	Kuai (Lihue)	\$1M - \$10M	Unrestricted	IFB
562910	FY18 4Q	TBD	W9128A-18-R-0005	Munitions & Explosives of Concern Single Award Task Order Contract (SATOC) - Waikola Maneuver Area	While the projects will be predominatntly at the Former Waikoloa Maneuver Area on the Island of Hawaii, the project areas include all the Hawaiian Islands, territories of Guam, American Samoa and Commonwealth of the Northern Mariana Islands, as well as the Freely Associated States including the Republic of Palau, Federal States of Micronesia, and the Republic of the Marshall Islands.	Oahu	\$95M	SB	RFP
237310	FY18 4Q	FY18 4Q	<a href="#">W9128A-18-R-0006</a>	Repair Mt. Ka'ala & Maluhia Intersection	Correct traffic signal system deficiencies such as replace existing light signal heads, replace existing wiring, conduits, controllers, and cabinets. Improve existing paved access road. Realign roadway away from failed slope areas, excavate embankments, improve culvert structure at stream crossing, paving, striping, signage, drainage, guard rails, etc.	Oahu (Ft DeRussy)	\$1M - \$10M	Unrestricted	RFP
237990	FY18 4Q	FY18 4Q	<a href="#">W9128A-18-Z-0013</a>	Hahaione Construction Repair of Flood Control	Design build firm fixed price project in two separate reaches, each with a unique scope of work to restore the channel and incline to its pre-storm conditions.	Oahu (Hawaii Kai)	\$1M - \$10M	SB	RFP